

WALL FINISHES

All walls to be painted with minimum 1 mist coat and 2 full coats. Unless otherwise specified:

General - All walls to be painted in Dulux Vinyl Matt Emulsion White (RAL 9010) unless other wise note (see Feature Walls) Laboratory and Workshop areas to be painted in Dulux Trade Diamond Eggshell (RAL 9010) unless other wise noted. Shower room areas to be painted in Dulux Diamond Matt (RAL 9010).

Wall Tiling - 200x 200 ceramic wall tiles. Pavigres P21 ref PC119. . Colour Uni Sol. Full height

General Splashbacks - uPVC washable panel to rear of all hand wash basin & sinks (except to IPS laminate lined walls) and drench shower. Altro Whiterock Splashback or equal and approved Approx 600mm high and extend 100mm to either side of basin/sink. 1200 wide, full height to Drench shower. Colour: White. Fixed direct with AltroFix W139 polyurethane all over adhesive.

Coloured Splashbacks - uPVC washable panel . Altro Whiterock Splashback or equal and approved Full height between base unit and cupboards. Colour: TBC. Fixed direct with AltroFix W139 polyurethane all over adhesive.

Anechoic Foam - anechoic foam lined chamber by specialist fitout contractor with removable acoustic panel to window to control annex 101.


100 dB EMC (Electro Magnetic) shielding wallng by specialist EMC specialist fit out contractor) refer to Outline

Catering - Hygenic PVC-u wall cladding. Altro Whiterock hygenic wall system or equal. Colour: Standard White. Fixed direct with AltroFix all over adhesive. Watertight jointing - Altro PVCU 'H' trim

No wall finishes to be applied

Feature Wall Painted - colour TBC

Applied Wall Graphics



P03 13.10.15 Updated in line with revised planning proposal Amended Stage 3+ information Drawing created date

ECM, University of Lincoln

2400 EC-MA-00-02-DR-A-35052

Phase 2 Second Floor Wall Finishes- 1:200@A1 S2-P03

> architecture / interiors / landscape Email • info@maber.co.uk Tel • 0115 9415555 maber.co.uk

issuing office Nottingham

maber

do not scale from this drawing• dimensions and levels to be checked on site by the contractor• all dimensions in millimetres unless otherwise noted • all levels in metres unless otherwise noted The title, copyright and confidential information in this document belongs to Maber Associates Limited. Copyright . All rights reserved. You may not reproduce this document or disclose it to others without the consent of Maber Associates Limited